

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u>	Located in:	Corner Code #	
<small>(County)</small>			
1. Public Land Survey	T <u>    </u> R <u>    </u>		<u>    </u>
	T <u>    </u> R <u>    </u>		<u>    </u>
	T <u>    </u> R <u>    </u>		<u>    </u>
	T <u>    </u> R <u>    </u>		<u>    </u>
2. Property Controlling in Section	S <u>36</u> T <u>53N</u> R <u>31W</u>		<u>9</u>
	S <u>36</u> T <u>53N</u> R <u>31W</u>		<u>8</u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>		<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>		<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No.         , Recorded Plat           
 5. Private Claims         

Nov 08 2001

I, Stephan J. Szyszkoski, in a field survey on         , 20     do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (9-Sec. 36) East 1/16 corner Section 36. Not established in the original survey.  
 (8-Sec. 36) West 1/16 corner, Section 36. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(9-Sec. 36) Established the corner midway and on a straight line between Center of Section 1319.63' west and Quarter corner 1319.63' east.  
 (8-Sec. 36) Established the corner midway and on a straight line between Quarter corner 1323.74' west and Center of Section 1323.74' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(9) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 6" Cedar S83E 20.6'      "1/16S BT" 8" Maple S04E 8.2'      do 22" Hemlock S68W 20.6'      do 7" Cedar N13W 3.0'      do Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	(8) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 7" Cedar N29E 8.1'      "1/16S BT" 5" Cedar S76E 24.8'      do 5" Y. Birch S10W 19.3'      do 12" Hemlock N32W 22.1'      do Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski Date 3/19/02  
 Surveyor's Michigan License No. 33986