

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 53N R 31W L12

T _____ R _____ _____

T _____ R _____ _____

T _____ R _____ _____

2. Property Controlling in Section

S 36 T 53N R 31W 11

S _____ T _____ R _____ _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____ _____

S _____ T _____ R _____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Nov 08 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:

(L12) Center of Section 36. Not established in the original survey.

(11-Sec. 36) Southwest 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L12) Established the corner at the intersection of straight lines connecting opposite quarter corners. From the corner monumented, I found a 4"x4" wood post projecting 8 feet, placed by an unknown party, N51E 22.8'

(11-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L12) Set 1"IDx32" I.pipe with 4" alum.

MDNR cap. Blazed and scribed:

9" Sugar N26E 18.0' "C1/4 BT"

10" Y.Birch S60E 15.0' do

12" Y.Birch S50W 28.8' do

12" Cedar N60W 26.3' do

Set squared cedar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.

(11) Set 1"IDx32" I.pipe with 4" alum.

MDNR cap. Blazed and scribed:

6" Y.Birch S25E 24.9' "1/16S BT"

11" Hemlock S21W 45.8' do

11" Cedar S68W 21.7' do

8" Y.Birch N57W 15.0' do

Set squared cedar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Date

3/19/02

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management