

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Baraga  
 (County)

Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section  
 S 36 T 53N R 31W \_\_\_\_\_  
 S 36 T 53N R 31W \_\_\_\_\_  
 7

3. Miscellaneous Property in Sec.  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 12

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Nov 13 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (7-Sec. 36) North 1/16 corner between Sec. 36 T53N-R31W and Sec. 31 T53N-R50W. Established in 1973 by A.O. Enger midway between Section and quarter corners. 3"x5"x5.5' wood post witnessed by Cedar 5 S19W 2.5', Cedar 12 N32W 14.9'.  
 (12-Sec. 36) South 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (7-Sec. 36) Recovered the 1973 wood post as described and at record bearing and distance from the remaining Cedar NW BT. Verified the position of the corner post, it being 1319.72' south of the Section corner and 1319.72' north of the Quarter corner, and on a line between, and replaced it with a new monument described below.  
 (12-Sec. 36) Established the corner midway and on a straight line between the Center of Section 1319.62' north and the Quarter corner 1319.62' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx32" 1.pipe with 4" alum. MDNR cap. Blazed and scribed:  
 16" Hemlock N60E 24.8' 1/16S BT"  
 11" Cedar S32E 17.8' do  
 14" Hemlock S70W 37.8' do  
 13" Cedar (1973) N27W 14.7' do  
 Placed a squared cedar post adjacent.  
 Bearings are magnetic. Distances are to notch in lower blaze.

(12) Set 1"IDx32" 1.pipe with 4" alum. MDNR cap. Blazed and scribed:  
 8" Cedar N70E 15.1' 1/16S BT"  
 10" Cedar S47E 12.7' do  
 12" Hemlock S28W 30.2' do  
 7" Cedar N15W 9.4' do  
 Set squared cedar post adjacent.  
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 3/19/02

For the Michigan Department of Natural Resources - Office of Property Management