

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>36</u> T <u>53N</u> R <u>31W</u>	13
	S <u>36</u> T <u>53N</u> R <u>31W</u>	5
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

5 Nov 20 2001
 13 Nov 13 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		10	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration;
 (13-Sec. 36) Southeast 1/16 corner, Section 36. Not established in the original survey.
 (5-Sec. 36) North 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (5-Sec. 36) Established the corner midway and on a straight line between Quarter corner 1319.57' north and Center of Section 1319.57' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed and scribed:	(5) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed and scribed:
8" Cedar N42E 13.1' "1/16S BT"	11" Cedar N04E 23.9' "1/16S BT"
6" Cedar S58E 9.4' do	9" Cedar N75E 12.2' do
12" W. Pine S75W 22.9' do	7" Cedar S17W 8.2' do
9" B. Spruce N70W 15.3' do	8" Cedar S60W 7.3' do

Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 3/19/02
 Surveyor's Michigan License No. 33986