

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located in:	Corner Code #	
(County)			
1. Public Land Survey	T 53N R 31W	MC W. of L11	
	T 53N R 31W	L11	
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 20 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		10	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (MC West of L11) Meander corner between Sections 25 and 36. The original meander corner position was not recovered (8.77 chains west of the Quarter corner L11).

(L11) Quarter corner common to Sections 25-36. Established in 1846 by Wm. Ives. West between Sections 25&36...40.00 Set qr. Section post. Hemlock 6 S42E 10, Fir 4 N50W 29.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC West of L11) Established a witness corner to the record position of the original meander corner on the Section line between Sections 25 and 36 and 7.5757 chains (500.00 feet) west of the quarter corner. The section line was produced through the Quarter and Section corners to the east.

(L11) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner at record distance west of M11 and on a line parallel to the south line of Section 36, passing through M11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap in a rock mound. Blazed and scribed:

7" W.Birch N17E 13.1' "MC NBT"
 8" B.Spruce S76E 32.5' do
 9" W.Spruce S30E 10.7' do
 19" W.Pine S15W 20.4' do
 Set squared cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.

(L11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
 12" W.Birch N50E 16.8' "1/4S NBT"
 17" W.Pine S35E 5.8' do
 A Balsam Fir N30W 11.4' do
 A squared cedar post S26W 11.8' to C/L
 A squared cedar post S62W 10.9' to C/L
 Placed a squared cedar post adjacent to the monument. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 3/19/02