

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>36</u> T <u>53N</u> R <u>31W</u>	<u>14</u>
	S <u>36</u> T <u>53N</u> R <u>31W</u>	<u>4</u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 27 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (14-Sec. 36) South 1/16 corner between Section 36 T53N-R31W and Section 31 T53N-R30W. Established in 1973 by A.O. Enger midway and on line between Quarter and Section corners. 4"x4"x5.5' squared cedar post, scribed. Cedar 12 S79W 10.5', Cedar 15 S35E 12.2'. Corner recorded L1 of LCRCs P139, Baraga Co. Records.
 (4-Sec. 36) Northwest 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 36) Recovered the 1973 post as described in his record, in good condition and substantially at the position intended by Mr. Enger. Left the post in place and placed a MDNR monument midway and on a line of mean true bearing between Quarter corner 1319.73' north and Section corner 1319.73' south.
 (4-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:	(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
7" Cedar N66E 24.6' "1/16S BT"	8" Cedar N17E 3.2' "1/16S BT"
11" Hemlock N17W 3.7' do	12" Y. Birch South 10.1' do
The 1973 wits:	9" Cedar N76W 20.4' do
11" Cedar S84W 10.4' do	8" Cedar N31W 8.5' do
14" Cedar S33E 11.8' scribing visible	Set squared cedar post adjacent.
The 1973 post, scribed, North 0.5'	Bearings are magnetic. Distances are to notch in lower blaze.
Bearings are magnetic. Distances are to notch in lower blaze.	



Signed by Stephan J. Szyszkoski Date 3/19/02
 Surveyor's Michigan License No. 33986