

CONVEY OR
REMONUMENTATION

MAY 2 1997

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 4 26 PM '93

Sandy Schondelmayer

REGISTER OF DEEDS

002143

Register of Deeds Stamp & File Number

For corners in

<u>Barry</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>1N</u> R <u>8W</u>	<u>M-13</u>
	T <u>1N</u> R <u>7W</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: W.Oak, 14", N37°E, 47 links
D.O., 15", N73°W, 85 links

C.P.Co.: Found 3/4" Pipe from witness
18" Hickory, N30°W, 38.45 feet
Conc. Mon, North 33.20
in centerline road in line with
fence North
LCRC#127, 3/20/74

Pratt: Field Book series #1, Page 82, no date
8" B.O., S16°W, 42 links
6" B.O., N60°W, 71 links

Bowen: Stone & Crockery, 1876
12" Hickory, S75°E, 1.01 chain
8" B. Ash, N61°W, .92 chains

James L. King, reset solid iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found solid rebar as described by L.C.R.C. #127.
Concrete monument North, 33.23 feet
30" Hickory, N45°W, 38.39 feet. Found nail on Northeast side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" iron pipe with aluminum remonumentation cap.
Concrete monument - North 33.23 feet
30" Hickory, N45°W, 30.39 feet, found old witness nail in Northeast side.
16" Oak, N42°E, 49.74 feet, set 60p nail in West side.
Fence post, N52°W, 84.16 feet, set PK in south side.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Daniel M. Ryan Date September 8, 1993
Surveyor's Michigan License No. 34975

