

**SURVEY & REMONUMENTATION**

FEB 17 1998

**SECTION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74. Mich. P.A. 1970**

For corners in

BARRY  
(County)

Located In:

Co



**2645**

Page: 1 of 1  
12/16/1997 12:20P

Sandy Schondelmayer - Barry Co. LCRGR

ASSYRIA TOWNSHIP

1. Public Land Survey

T 1N R 7W E-13

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on APRIL 5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. MULLETT D.S. 1825  
ASPIN 12 N89-1/2°E 63; W. OAK 18 N36-1/2W 1.46  
1965 McPHERSON, CONSUMER POWER COMPANY 5/8 IRON RESET FROM EVIDENCE NOTED IN GOVERNMENT NOTES; 6" WHITE OAK, N2°W 55.90; 20" RED OAK, N50°E 68.35;  
36 FEET SOUTH OF NORTH RIGHT-OF-WAY FENCE; IN LINE WITH FENCE NORTH 15 FEET EAST OF CREEK WEST.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON BY McPHERSON 15 FEET EAST OF SMALL CREEK  
G.L.O. NOTES CALL FOR CORNER TO BE 0.5 CHAINS WEST OF CREEK  
McPHERSON IRON IS 2694.12 FEET EAST OF SOUTH 1/4 POST OF SECTION 32 AND 2595.65 FEET WEST OF SOUTH 1/4 POST OF SECTION 33.  
PERPORTIONATE DISTANCE BETWEEN SOUTH 1/4 POST OF SECTION 32 AND SOUTH 1/4 POST OF SECTION 33 PLACE CORNER 33 FEET WEST OF WHAT APPEARS TO BE THE ORIGINAL COURSE OF THE STREAM. ACCEPTED THIS LOCATION AS THE BEST EVIDENCE OF LOCATION OF ORIGINAL CORNER AND DISREGARDED McPHERSON IRON.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 SEPT. 97  
BRIAN REYNOLDS

BR  
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BARRY COUNTY REMONUMENTATION STAKE AND CAP AT PERPORTIONATE DISTANCE BETWEEN SOUTH 1/4 POST OF SECTION 32 AND SOUTH 1/4 POST OF SECTION 33 AND ON A PROJECTION OF THE BASELINE FROM THE SOUTH 1/4 POST OF SECTION 32 THROUGH THE NORTH 1/4 POST OF SECTION 5, T.1S., R.7W.  
3" OAK, N06°W 25.76 FEET, SET SPOTTER  
1" OAK, N57°W 14.53 FEET, SET SPOTTER  
2" OAK, N73°E 17.00 FEET, SET SPOTTER  
4" OAK, S14°E 57.84 FEET, SET SPOTTER  
5 FEET MORE OR LESS SOUTH OF CENTERLINE OF OLD ROAD BED.

Signed by [Signature]  
Surveyor's Michigan License No. 20704

Date NOV. 7, 1997

