

SURVEY & REMONUMENTATION

FEB 17 1998

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY (County)

Located In:



2646

Page: 1 of 1 12/16/1997 12:28P

Sandy Schondelmayer - Barry Co. LCRCR

ASSYRIA TOWNSHIP 1. Public Land Survey T 1N R 7W F-13 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R



4. Lot No. Recorded Plat 5. Private Claims

I, ROBERT R. CARR, in a field survey on APRIL 5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. MULLETT D.S. 1885 W. OAK 10 N77-1/2°E 2.28 DO 16 N57-1/2°W 98

Grid table with columns A-L and rows 1-13. Contains numbers 6-36 and a dot in cell 12,33.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 Sept. '97 BRIAN REYNOLDS

BR COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN CENTERLINE OF EAST AND WEST BITUMINOUS ROAD SURFACE ON FILL IN MARSHY AREA. NO NORTH AND SOUTH OCCUPATION OR OTHER EVIDENCE OF CORNER LOCATION EVIDENT. THIS IRON IS 2630.71 FEET SOUTH OF IRON STAKE FOUND AT THE CENTER OF SECTION 33, 2636.07 FEET WEST OF SOUTHEAST CORNER OF SECTION 33 AND 2644.88 FEET EAST OF SOUTHWEST CORNER OF SECTION 33. ROAD BED DEVIATES TO NORTH THROUGH MARSHY AREA WHERE CORNER IS LOCATED COMPARED TO PROJECTIONS OF THE CENTERLINE FROM EAST AND WEST. A PROJECTION OF THE BASELINE FROM THE SOUTHWEST CORNER OF SECTION 33 EAST THROUGH THE NORTHWEST CORNER OF SECTION 4, T.1S., R.7W. PLACES THE LOCATION OF THIS CORNER 10.42 FEET SOUTH OF THE FOUND IRON AND 2641.13 SOUTH OF IRON FOUND AT CENTER OF SECTION 33. THIS LOCATION ALSO FITS WELL WITH THE PROJECTIONS OF ROAD CENTERLINE FROM EAST AND WEST. ACCEPTED THIS LOCATION AS BEST EVIDENCE OF CORNER AND SET BARRY COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX 0.5 FEET BELOW SURFACE OF GRAVEL SHOULDER. SOUTHDGE OF BITUMINOUS SURFACE, NORTH 1.4 FEET 16" OAK, N50°E 97.18 FEET, SET SPOTTER 14" OAK, N66°E 94.60 FEET, SET SPOTTER TWIN 12" & 14" OAK, S71°W 119.48 FEET, SET SPOTTER 8" OAK, S44°W 125.32 FEET, SET SPOTTER.



Signed by [Signature] Surveyor's Michigan License No. 20704

Date NOV. 7, 1997