

DEC 7 4 26 PM '93

Sandy Schindelmaier
 REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

002127

For corners in
Barry
 (County)

Located In: Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>1N</u> R <u>7W</u> | <u>G-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GL0: 14" Black Ash, S57°E, 18 links Heath - 1903: 6" Black Ash, N17½°E, 1 chain, 25 links
 18" Birch, N71°W, 33 links 10" Maple, N10½°W, 1 chain, 8 links
 Liber 3, Page 84 & 85

Lester: Found ½" iron rod in monument box.
 Northeast side U.P., Southeast, 130.19 feet
 North edge steel sign post, Southwest, 49.94 feet
 Centerline street sign, Northwest, 60.05 feet
 South edge sign post, Northeast, 55.31 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron rod in Monument box
 On centerline of M-66.

SURVEY &
 REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found ½" iron in monument box. Replaced with Barry County remonumentation iron & cap.
 Chiseled "X" & drilled hole in top of concrete curb, N45°W, 50.71 feet
 Chiseled "X" & drilled hole in top of concrete curb, N55°E, 42.52 feet
 Chiseled "X" & drilled hole in top of concrete curb, S50°E, 51.23 feet
 Chiseled "X" & drilled hole in top of concrete curb, S44°W, 43.03 feet



Signed by [Signature] Date September 8, 1993

Surveyor's Michigan License No. 34975