

FEB 03 1999

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

BARRY (County) ASSYRIA TOWNSHIP

Located In:

Corner Code #

1. Public Land Survey

T 1N R 7W

I-11

2. Property Controlling in Section

S T R S T R

3. Miscellaneous Property in Sec.

S T R S T R



2723

Page: 1 of 1 12/15/1998 08:27A

Sandy Schondeimayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 26, 27, 34 & 35

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY MUSGROVE EVANS D.S. 1826

LEE COBB, COUNTY SURVEYOR, 1914, CORNER OF FENCE SAID TO HAVE BEEN PUT ON THE SURVEY MADE BY A.C. WILSON IN 1874 OR 1879, COBB WAS TOLD BY MR. ED BERRY THAT WILSON ESTABLISHED CORNER FROM WHAT HE THOUGHT WERE STUMPS OF U.S. BEARING TREES. (LIBER 1, PAGE 384, COUNTY SURVEYOR RECORDS)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE WITH 1/2" IRON AND CAP BY BRYAN, P.S. #25832, INSIDE PIPE. PIPE ON WEST SIDE OF OLD ROTTED OFF FENCE CORNER. OLD WIRE IN TREES AND ON GROUND N, S, E & W, WITH NO SIGN OF ANOTHER FENCE CORNER. I ACCEPTED THIS TO BE SAME FENCE CORNER AS REFERENCED BY COBB IN 1914.

REMOVED IRON AND SET BARRY COUNTY REMONUMENTATION STAKE AND CAP INSIDE PIPE.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON NOV 9, 1998 BR BRYAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP INSIDE 1" PIPE 11" SWAMP MAPLE, N37°E 26.08 FEET ( SET SPOTTER ) 7" SOFT MAPLE, N85°E 5.15 FEET 7" MAPLE, S68°W 17.40 FEET 7" MAPLE, S20°W 35.12 FEET OLD WIRE IN TREES N, S, E & W AND ON GROUND

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]

Date November 23, 1998

Surveyor's Michigan License No. 20704

ROBERT R. CARR

Grid table with columns A-M and rows 1-13. A dot is present at row 11, column I.