

FEB 03 1999

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

BARRY (County)

Located in:

Corner Code #

ASSYRIA TOWNSHIP 1. Public Land Survey

T 1N R 7W

1-12

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R



Sandy Schondelmayer - Barry Co. LCRCR

2725

Page: 1 of 1 12/15/1998 08:27A

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 34 & 35

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY MUSGROVE EVANS, D.S. 1826 KING, P.S. #14766, 1972, SET 1/2" IRON, L.C.R.C. NO. 51 BARRY COUNTY ROAD COMMISSION 1972, IRON WITH SAME WITNESSES AS KING. SURVEY BY R. CARR, P.S. #20704, 1986, TIED TO SAME CORNER PER L.C.R.C. NO. 51

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2 IRON MATCHING WITNESSES PER KING, 1972 AND CARR, 1986.

REPLACED 1/2" IRON WITH BARRY COUNTY REMONUMENTATION STAKE AND CAP.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON OCTOBER 12, 1998 B.R. COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP 7" HICKORY, N52°E 19.11 FEET (NAIL AND SPOTTER) 28" HICKORY, N28°W 24.03 FEET (NAIL AND SPOTTER) 10" HICKORY, S70°W 29.85 FEET (NAIL AND SPOTTER) R.R. RAIL POST, S10°W 29.42 FEET

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]

Date NOVEMBER 23, 1998

Surveyor's Michigan License No. 20704 ROBERT R. CARR