

FEB 03 1999

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for BARRY (County), Located In: T 1N R 7W, Corner Code #: I-13, and checkboxes for 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims.



2724 Page: 1 of 1 12/15/1998 08:27A

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on OCTOBER 5, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHEAST CORNER OF SECTION 34, SOUTHWEST CORNER OF SECTION 35 A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY JOHN MULLETT, D.S. 1825 DEKEYSER, 1965, SURVEY FOR CONSUMERS POWER COMPANY, SET 5/8" IRON 768.25 FEET EAST OF NORTH 1/4 POST OF SECTION 3, TOWN 1 SOUTH, RANGE 7 WEST AND ON PROJECTION OF NORTH LINE OF NORTHWEST 1/4 OF THE SECTION 3 L.C.R.C. NO. 55 BY KING, P.S. 14766, 1972, 5/8" IRON MATCHING CONSUMERS POWER COMPANY WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" IRON IN MONUMENT BOX MATCHING REMAINING WITNESSES FROM L.C.R.C. NO. 55 PLACED BARRY COUNTY REMONUMENTATION CAP ON IRON IN EXISTING MONUMENT BOX.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON OCT 12, 1998 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUEMNTATION CAP ON IRON IN MONUMENT BOX UTILITY POLE, N10°W 28.11 FEET (SET SPOTTER) 20" WALNUT, S20°E 21.90 FEET (SET SPOTTER) 30" MAPLE, S72°W 49.15 FEET (SET SPOTTER) SOUTHEAST CORNER OF CONCRETE WALL FOR CULVERT, N68°W 55.6 FEET IN LINE FENCE TO NORTH 3' ± SOUTH OF CENTERLINE OF ROAD.

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature] Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOVEMBER 23, 1998