

FEB 03 1999

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY (County)

Located In:

Corner Code #

ASSYRIA TOWNSHIP 1. Public Land Survey

T 1N R 7W T R T R T R S T R S T R S T R

J-9



2722

Page: 1 of 1 12/15/1998 08:27A

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 23 & 26

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY MUSGROVE EVANS, D.S. 1826 W.O. 16" S73E 60 LKS, W.O. 10" S02E 72 LKS.

R. CARR, P.S. #20704, 1993 FOUND TRIANGULAR STONE WITH FAINT "X" ON FACE IN EAST-WEST FENCE LINE AND 17.3 FEET EAST OF FENCE TO SOUTH, RAN NORTH & SOUTH 1/4 LINE AND FOUND 1/4 LINE OCCUPATION THROUGH CENTER OF SECTION TO SUPPORT LOCATION OF STONE.

SET 1/2" IRON IN PLACE OF STONE AND LEFT STONE BESIDE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ABOVE WITH STONE BESIDE AND REPLACED 1/2" IRON WITH BARRY COUNTY REMONUMENTATION STAKE AND CAP

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

NOV 9, 1998 BR BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP WITH STONE BESIDE.

5" CHERRY, N21°W 37.22 FEET (SET NAIL AND SPOTTER) 6" CHERRY, N78°E 5.63 FEET (SET NAIL AND SPOTTER) 4" CHERRY, S30°E 31.34 FEET (SET NAIL AND SPOTTER) 5" CHERRY, N83°W 26.35 FEET (SET NAIL AND SPOTTER)

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]

Date NOVEMBER 23, 1998

Surveyor's Michigan License No. 20704 ROBERT R. CARR