

FEB 03 1999

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION For corners in

BARRY (County)

Located in:

Corner Code #

ASSYRIA TOWNSHIP

1. Public Land Survey

T 1N R 7W

J-11

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R



2727

Page: 1 of 1 12/15/1998 08:27A

Sandy Schondelmayer - Barry Co. LCROR

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 26 & 35

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY MUSGROVE EVANS, D.S. 1826 R. CARR, P.S. #20704, 1993, FOUND 4" DIAMETER HOLLOW CLAY TILE RAN NORTH AND SOUTH 1/4 LINE, SECTION 26 AND FOUND TILE TO FIT WELL WITH NORTH AND SOUTH 1/4 LINE OCCUPATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" HOLLOW TILE PER ABOVE. SET BARRY COUNTY REMONUMENTATION STAKE AND CAP IN CENTER OF TILE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP IN 4" HOLLOW CLAY TILE. R.R. TIE POST, S40°W 6.10 FEET (NAIL AND SPOTTER) 40" OAK, N02°W 10.75 FEET (NAIL AND SPOTTER) 20" CHERRY, S80°W 18.0 FEET 10" OAK, N50°W 20.60 FEET (NAIL AND SPOTTER) 5" CHERRY, S40°W 40.02 FEET (NAIL AND SPOTTER)

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON OCT. 12, 1998 BR COUNTY SURVEYOR BRIAN REYNOLDS

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and a circled 0 in row 11, column J.



Signed by [Signature]

Date NOVEMBER 23, 1998

Surveyor's Michigan License No. 20704 ROBERT R. CARR