

SURVEY & REMONUMENTATION

FEB 03 1999

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY

Located In:

Corner Code #

(County)

ASSYRIA TOWNSHIP

Public Land Survey

T 1N R 7W

J-13

T R

T R

T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R



2726

Page: 1 of 1 12/15/1998 08:27A

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTH 1/4 POST SECTION 35

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY JOHN MULLET, D.S. 1825

COUNTY SURVEYOR RECORDS, W.O. 8 N3/4E, NO NAME OR DATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SOUTHWEST AND SOUTHEAST CORNERS OF SECTION 35 AS ESTABLISHED IN CONSUMERS POWER SURVEY, 1965

SET 1/4 POST AT MID-POINT ON LINE, THIS LOCATION FITS OCCUPATION TO NORTH WELL, ALSO SPLIT OF WEST 1/2 MILE FITS 1/8 LINE OCCUPATION TO NORTH.

SET BARRY COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

OCTOBER 12 1998 B.R. COUNTY SURVEYOR BRIAN REYNOLDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX. UTILITY POLE, S02°W 53.28 FEET 15" HICKORY, S40°E 39.29 FEET UTILITY POLE, N45°E 24.38 FEET (SET SPOTTER) 6" MAPLE, N50°W 42.55 FEET

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]

Date NOVEMBER 23, 1998

Surveyor's Michigan License No. 20704 ROBERT R. CARR

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and letters B, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36.