

FEB 03 1999

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY Located In: _____ Corner Code # _____
 (County)
 ASSYRIA TOWNSHIP
 1. Public Land Survey T 1N R 7W K-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____



2729 Page: 1 of 1 12/15/1998 08:27A

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on OCTOBER 5, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTION 25, 26, 35 & 36
A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL CORNER SET BY MUSGROVE EVANS 1826
KAY DON FLUKE, P.S. #18988, 1988, FOUND REMAINS OF ROTTED POST (FENCE CORNER).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" IRON AND CAP BY FLUKE, P.S. 18988, AT INTERSECTION OF FENCES EAST, WEST AND NORTH.
REPLACED 1/2" IRON BY FLUKE WITH BARRY COUNTY REMONUMENTATION STAKE AND CAP WITH RING OF STONES AROUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
BARRY COUNTY REMONUMENTATION STAKE AND CAP IN RING OF STONES
10" OAK, S80°E 11.17 FEET (SET SPOTTER)
12" ASH, S35°W 17.38 FEET (SET SPOTTER)
11" CHERRY, S77°W 16.85 FEET (SET SPOTTER)
11" CHERRY, N08°E 18.36 FEET (SET SPOTTER)
24" OAK, N38°W 34.68 FEET (SET SPOTTER)
IN LINE WITH FENCE NORTH
IN FENCE EAST AND WEST.
AND THIS IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON Nov 9, 1998 BSR COUNTY SURVEYOR BRIAN REYNOLDS



Signed by [Signature] Date NOVEMBER 23, 1998
Surveyor's Michigan License No. 20704 ROBERT R. CARR