

DEC 7 4 26 PM '93

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmarer
REGISTER OF DEEDS

002131

Register of Deeds Stamp & File Number.

For corners in
Barry
(County)

Located In: Corner Code #/

- 1. Public Land Survey T 1N R 7W K-12
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey; instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 9" Black Oak, N32°E, 8 links
White Oak, S27°W, 1 chain

P. McP., September, 1971: Found stone
4 feet North of East and West fence
24" Stump, S40°W, 24.79 feet
10" Oak, S10°W, 34.00 feet
12" Oak, S10°E, 18.00 feet
LCRC #10

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found oblong, pointed stone with small "X" scribed in top.
Found two witnesses from P.McP in 1971.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found oblong, pointed stone with small "X" scribed in top. Replaced with Barry County Remonumentation iron & cap.
60p nail in West side of 18" Oak, S15°E
60p nail in East side of 16" Oak, S21°W
60p nail in South side of 22" Maple, S74°W, 25.88 feet
60p nail in Southeast side of 8" Maple, N51°E, 6.30 feet



Signed by [Signature] Date September 8, 1993

Surveyor's Michigan License No. 34975