

SURVEY & REMONUMENTATION

MAR 09 1999

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

MAR 09 1999

SECTION

For corners in

BARRY (County) ASSYRIA TOWNSHIP 7. Public Land Survey

Located In:

T 1N R 7W

Corner Code #

K-13



2721

Page: 1 of 1 12/15/1998 08:27A

Sandy Schonhelmayer - Barry Co. LCRCR

- 2. Property Controlling in Section
3. Miscellaneous Property in Sec.
S T R
S T R
S T R
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SE CORNER OF SECTION 35, SW CORNER OF SECTION 36

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY JOHN MULLETT, D.S. 1825 CORNER REESTABLISHED WITH CONSUMERS POWER SURVEY, 1965 SET "T" IRON KING, P.S. #14766, 1972, RECOVERED C.P.CO. "T" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON PER CONSUMERS POWER COMPANY SURVEY 1965 AND KING 1972.

REPLACED "T" IRON WITH BARRY COUNTY REMONUMENTATION IRON AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION IRON AND CAP 6" OAK, S45°W 36.21 FEET (SET SPOTTER) 10" OAK, N60°W 44.40 FEET (SET SPOTTER) 5" HICKORY, N05°W 11.95 FEET (SET SPOTTER) 12" CHERRY, S69°E 12.71 FEET (SET SPOTTER)

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Grid table with columns A-M and rows 1-13. Cell (12, 12) contains a circled '1'.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

Nov 9 1998 BR BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]

Date NOV 30, 1998