

Dec 7 4 26 PM '93

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmarper
REGISTER OF DEEDS

002132

For corners in

Barry

(County)

Located In:

Corner Code #/

1. Public Land Survey

T 1N R 7W

L-13

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____

Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel M. Ryan, in a field survey on September 8, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 10" White Oak, N84°E, 12 feet
8" White Oak, N56°W, 32 feet

C.P.Co.: Found 1/2" pipe

Telephone pole, S85°E, 7.30 feet
10" Hickory, N80°W, 17.60 feet
9" Hickory, S40°W, 42.36 feet
50 feet Northwesterly at right angles to centerline of M-78.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron pipe
50 feet, more or less, from centerline of M-78.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" pipe, replaced with Barry County Remonumentation iron and cap.
60p nail on East side of 10" Hickory, S48°W, 42.37 feet
P.K. on Northeast side of 14" Hickory, N53°W, 16.98 feet
P.K. on East side of 18" Walnut, N32°E, 37.54 feet
P.K. on East side of Walnut, N43°W, 4.29 feet

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by [Signature]

Date September 8, 1993

Surveyor's Michigan License No. 34975