

DEC 7 4 26 PM '93

Sandy Schondelmayer

REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
(County)

Located In:

Corner Code =#

1. Public Land Survey

T 1N R 7W M-11

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
In Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

002133

Sequence # 1

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 6" Black Oak, S20°W, 36 feet
5" White Oak, N73°W, 13 feet

C.P.Co.: Found plow point 2 feet below fill, set "T" iron over.
Edge of Road, N 11 feet
Edge of Road, S 9 feet
Telephone pole, N53°W, 53.4 feet
22" Hickory Nut, S15°W, 36.4 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron in gravel road

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bent 3" top of "T" iron over and down. Set 3/4" Barry County Remonumentation iron and cap.
6" Hickory, S49°E, 44.63 feet. Set 60p nail in North side.
14" Hickory, S20°E, 45.82 feet. Found nail & spotter on West side.
18" Oak, S34°W, 43.36 feet. Found nail & spotter on East side.
10" Oak, N3°W, 34.82 feet. Found nail & spotter on East side.
1', more or less, South of centerline of East/West road.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by *Daniel M. Ryan* Date September 8, 1993
Surveyor's Michigan License No. 34975