

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 7 4 26 PM '93

Sandy Schondelmayer
REGISTER OF DEEDS

For corners in

Barry

(County)

Located In:

Corner Code \neq

1. Public Land Survey

T 1N R 7W

M-12

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

002134

Register of Deeds Stamp & File Number

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey, instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 18" White Oak, N28 $\frac{1}{2}$ °W, 20 feet
18" White Oak, S14°W, 47 feet

Robert Carr, 1972:
 $\frac{1}{2}$ " Iron Road
0.5 feet South of East/West fence
1.5 feet West of North & South fence
20" Hickory, S2°E, 12.65 feet
12" Hickory, N70°W, 11.00 feet
26" Oak, N02°E, 19.65 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found $\frac{1}{2}$ " iron
Used witnesses from Robert Carr, 1972

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found $\frac{1}{2}$ " iron rod and replaced with Barry County Remonumentation iron & cap.
60p nail in South side of 8" maple, S82°E, 20.69 feet
50p nail in West side of 30" Oak, N02°E, 19.65 feet
Nail & spotter in Northeast side of 18" Hickory, N70°W, 11.00 feet
Nail & spotter in West side of 24" Hickory, S02°E, 12.65 feet



Signed by [Signature]

Date September 8, 1993

Surveyor's Michigan License No. 34975