

DEC 7 4 26 PM '93

Sandy Schondelmaier  
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

002135

Register of Deeds Stamp & File Number

For corners in

Barry

(County)

Located In:

Corner Code #

1. Public Land Survey

T 1N R 7W

M-13

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_

Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2, above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 15" White Oak, N55°E, 81 feet  
16" White Oak, N74°W, 188 feet

C.P.Co. (1966): 3/4" pipe in South side of 24" Hickory in North, East & West fence  
16" Hickory, N87°W, 26.47 feet  
16" Hickory, N88°W, 44.10 feet

Used by Robert Carr in 1972, LCRC#34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe in base of 26" hickory.

SURVEY &  
REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Found 3/4" pipe in base of 26" hickory, drove Barry County Remonumentation iron inside, set 60p nail in North side of 8" hickory, East 47.34 feet.  
Nail & spotter on North side of 16" Hickory, N87°W, 26.47 feet  
60p nail on South side of 16" Hickory, N88°W, 44.10 feet  
60p nail in Southeast side of 24" Hickory, S45°W, 189.47 feet



Signed by [Signature]

Date September 8, 1993

Surveyor's Michigan License No. 34975