

FEB 03 1999

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN:

LOCATED IN:

CORNER CODE #

Barry COUNTY

1. Public Land Survey T 1N R 8W

A-3

SECTION COR. COMMON TO SECTION'S 6 & 7 T..... R.....

JOHNSTOWN TOWNSHIP T..... R.....

T..... R.....



2730

Page: 1 of 1
12/15/1998 09:31A

Sandy Schondelmayer - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

2. Property Controlling in section S.....T.....R.....

S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No. Recorded Plat.....

5. Private Claims.....

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. BARRY COUNTY DOSSIER FOR REMONUMENTATION

G.L.O.-WEST BETWEEN SEC 6 & 7,
79.37 WEST BOUNDARY 52 LINKS NORTH OF CORNER OF 1 & 12
A WHITE ASH 14" N.37-1/2E. 18
DO. 10" S.78E. 36 LINKS
MUSGROVE EVANS D.S. 1826 (R8W, P. 39)

COUNTY SURVEYOR RECORDS
TOOK NEW BEARING: HICK 9" N.16W. 92
RORK, APRIL 7, 1866 (L.2, P.95)

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
DEC 7, 1998 BR
BRIAN REYNOLDS COUNTY SURVEYOR

* NO OTHER CORNER HISTORY *

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF THE ORIGINAL CORNER OR SUBSEQUENT RESTORATION.

SET BARRY COUNTY REMONUMENTATION IRON WITH CAP ON OCCUPATION LINE TO EAST AND ON LINE WITH FENCE LINE OCCUPATION TO NORTH ON EDGE OF LAKE.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 12-07-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-PK & TAG IN NE SIDE 14" ASH WEST 47.65'
-PK & TAG IN NE SIDE 12" ASH S40°W 35.30'
-FACE 4" STEEL FENCE POST S30°W 48.55'
-PK & TAG IN NW SIDE 14" CHERRY S35°E 37.82'
-CL ROAD WEST 14' +/-
-M-3, BARRY TOWNSHIP SOUTH 34.32'
-PK & TAG IN NW SIDE 20" WALNUT N85°E 21.24'

Raymond Moored

Date 12/10/98

Surveyors License No. 26463

