

FEB 08 1999

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN:

LOCATED IN:

CORNER CODE #

1. Public Land Survey

T. 1N R. 8W

A-4

WEST SECTION COR.
TO SECTION 7

T. R.

JOHNSTOWN TOWNSHIP

T. R.

T. R.



2731

Page: 1 of 1
12/15/1998 08:31A

Sandy Schondelmayer - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

2. Property Controlling
in section

S. T. R.

S. T. R.

3. Miscellaneous
Property in Sec.

S. T. R.

4. Lot No. Recorded Plat.

5. Private Claims.

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. BARRY COUNTY DOSSIER FOR REMONUMENTATION

NOT SET BY G.L.O.

NO CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

DEC 7, 1998
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF THE ORIGINAL CORNER OR SUBSEQUENT RESTORATION.

SET BARRY COUNTY REMONUMENTATION IRON WITH CAP IN CENTERLINE ROAD ON OCCUPTION LINE TO EAST.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL RESSTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 12-07-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

-PK & TAG IN NE SIDE 16" CHERRY N40°W 34.91'

-PK & TAG IN SE SIDE 30" ASH S25°W 52.61'

-PK & TAG IN SE SIDE 22" MAPLE N40°E 43.41'

-PK & TAG IN SW SIDE 24" OAK S20°E 71.83'

-ON OCCUPATION LINE TO EAST

-IN C/L ROAD

-M -4, BARRY TOWNSHIP SOUTH 30.03'

Raymond Moored

Date 12/10/98

Surveyors License No. 26463

