

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 4 26 PM '93

Sandy Schondelmar
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

002137

Register of Deeds Stamp & File Number

corners in
Barry
(County)

Located In: Corner Code #
T 1N R 8W A-13
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Public Land Survey

Property Controlling
in Section
Miscellaneous
Property in Sec.

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Daniel M. Ryan, in a field survey on September 8, 19 93,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO: 10" White Oak, N35½°E, 22 links
12" White Oak, N27°W, 20 links

C.P.Co.: 1" Pinch pipe with stones - 1965
1' South of fence corner fences North, East and West
24" Oak, N70°E, 16.46 feet
6" Maple, N15°E, 9.55 feet
18" Oak, N5°E, 24.30 feet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pinch Pipe - Bearings shown are magnetic.

10" Maple, N25°E, 9.46 feet, nail in West side.
1'± South of East & West fences, in line with fence North.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced pipe with 3/4" iron rod and aluminum remonumentation cap.

10" Maple, N25°E, 9.46 feet, nail in West side.
5" Oak, S43°E, 32.20 feet, nail on Northeast side.
8" Oak, S40°W, 15.43 feet, nail in East side.
8" Oak, S56°W, 22.32 feet, nail in East side.



Surveyed by [Signature] Date September 8, 1993

Surveyor's Michigan License No. 34975