

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 4 26 PM '93

Sandy Schondelmaier
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

002139

Register of Deeds Stamp & File Number

corners in
Barry
(County)

Located In: Corner Code #

Public Land Survey

T 1N R 8W C-13

Property Controlling
in Section

S T R

Miscellaneous

S T R

Property in Sec.

S T R

Lot No. _____, Recorded Plat. _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Daniel M. Ryan, in a field survey on September 8, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as assessed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GL0: 14" White Oak, N64°E, 264 links County Road Comm.: iron
12" White Oak, N20½°W, 401 links 24" Hickory, S18°E, 82.2'
18" Hickory, S55°E, 70.4'

C.P.Co.: Found 1" iron - accepted as perpetuation of true position.
U-pole S60° W, 32.75 feet in centerline of road East, West & North.
U-pole, N25°W, 77.56 feet
U-pole, N50°E, 84.20 feet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron road
U-pole North 25°W, 77.47 - nail and spotter
U-pole, N50°E, 85.32 - nail and spotter
On centerline of roads, North, East & West

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron with 3/4" iron & aluminum remonumentation cap.
Fence corner, S75°W, 86.18 feet, PK on Southeast side.
18" Hickory, S73°E, 70.68 feet, 60p nail on Southwest side.
U-pole, N25°W, 77.47, nail & spotter on West side.
U-pole, N50°E, 85.32 feet, Nail and spotter on Southeast side.



Recorded by Daniel M. Ryan Date September 8, 1993

Surveyor's Michigan License No. 34975