

SURVEY & REMONUMENTATION

FEB 17 1998



2629

Page: 1 of 1
12/16/1997 12:15P

Sandy Schonhelmayer - Barry Co. LCRCR

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in BARRY COUNTY	Located In:	Corner Code #
1. Public Land Survey N 1/4 COR TO SEC. 5 JOHNSTOWN TWP.	T..1N R..8W T..... R..... T..... R..... T..... R.....D-1.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RAYMOND MOORED, in a field survey on OCTOBER 5, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER NOT ESTABLISHED BY G.L.O.
 POWER LINE SURVEY BY CONS. POWER CO., CIRCA 1950, CORNER WITNESSED BY
 2" X 2" X 24" GUARD STAKES 25' NORTH AND SOUTH. 25' JOG TO SOUTH 1/4 CORNER, SEC. 32
 BALTIMORE. (NO DESCRIPTION OF CORNER MONUMENT).
 NO OTHER HISTORICAL DATA AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 MEASURED FROM STATIONING ON OLD CONS. POWER CO. POLE LINE SURVEY ALONG N & S
 1/4 LINES OF SEC 32 BALTIMORE AND SEC. 5 JOHNSTOWN. DUG AT APPROXIMATE INTERSECTION
 OF TOWN LINE AND 1/4 LINES AND FOUND LARGE FLAT STONE IN PIT OF STONES. SET BARRY COUNTY
 REMON. IRON W/ CAP OVER STONE IN PIT OF STONES.

ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 13 Aug, '96 BR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
 NAIL IN NW SIDE POWER POLE S45W 9.80'
 NAIL IN N SIDE 12" BEECH S65W 83.63'
 NAIL IN N SIDE 6" BEECH N80E 49.14'
 IN LINE WITH OCCUPATION LINE TO SOUTH
 SOUTH 1/4 COR (D-13), T2N, R8W WEST 25.00'

Signed by Raymond Moored
 Surveyor's Michigan License No. 26463

Date 12/11/97

