

DEC 7 4 26 PM '93

Sandy Schondelmarer
 REGISTER OF DEEDS

002140

Register of Deeds Stamp & File Number

BARRY COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
 (County)

Located In: Corner Code #

1. Public Land Survey

T 1N R 8W D-11

T _____ R _____ _____

T _____ R _____ _____

T _____ R _____ _____

2. Property Controlling in Section

S _____ T _____ R _____ _____

S _____ T _____ R _____ _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____ _____

S _____ T _____ R _____ _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 8" White Oak, S28°W, 10 links
 10" White Oak, N28°E, 13 links
 County Road Commission: Stone & brick
 Cor. iron post, S45°E, 33.00 feet
 40" Elm, N45°E, 39.30 feet
 Concrete Post, West 27.20 feet
 Mon. Box Installed, 2/9/73

C.P. Co.: Set 3/4" Sq. iron rod using old witnesses from 1905 Cobb survey. 5'± of centerline North & South Rd. In line with fence West. Corner of House found N40°E, 92.85' U-pole, N25°W, 102.85 feet U-pole, N45°E, 29.00 feet Cor. Iron Post, S45°E, 32.57 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Square iron rod from old C.P. Co. witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" iron and aluminum cap, Barry County Remonumentation.

Witnessed as follows:
 U-pole, N18°W, 102.85 feet, nail and spotter on East side.
 Southwest corner house found, N37°E, 92.85 feet.
 1/2" Capped iron, 34975, S42°E, 46.08 feet.
 18" Cherry, S20°W, 76.95 feet, 60p nail on East side.

SURVEY &
 REMONUMENTATION

APR 05 1994

COMMISSION



Signed by [Signature]

Date September 8, 1993

Surveyor's Michigan License No. 34975