

**SURVEY &
REMONUMENTATION**

FEB 17 1998



Sandy Schondelmayer - Barry Co. LCRGR

2634

Page: 1 of 1
12/16/1997 12:15P

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in BARRY COUNTY	Located In:	Corner Code #
1. Public Land Survey 1/4 COR COMMON TO SEC. 4 & 5 JOHNSTOWN TWP.	T..1N R..8W T..... R..... T..... R..... T..... R.....	...E-2.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	●	4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

RAYMOND MOORED, in a field survey on OCTOBER 5, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO MUSGROVE EVANS, D.S. 1826 SET POST. B.OAK 18 N89E 43; W. OAK 20 S68W 34
PRATT 1885 STAKE; DOUBLE HICKORY 8 N7E 36 1/2; W. ASH 10 S14 1/2 E 55
COBB JUNE 9, 1913 FD. GAS PIPE FOR CORNER. NO WITS.
CO. ROAD COMM. 1931 PIFER ROAD PLANS, PG. 7; IRON PIPE; 8" APPLE N55E 40.3'
W. TRUNK 18" TWIN HICKORY N7E 24'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 2" PIPE 4' DEEP PER CO. ROAD COMM INFORMATION STATED ABOVE.
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP OVER 2" PIPE.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 13 May '96 *RR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
NAIL IN NE SIDE 15" SHAGBARK HICKORY N45W 44.80'
NAIL IN W SIDE 12" CORNER FENCE POST NORTH 38.35'
NAIL IN E SIDE POWER POLE S10W 36.91'
NAIL IN W SIDE 5" ASH SOUTH 55.30'

Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 12/11/97

