

BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 7 4 26 PM '93

Sandy Schondelmar  
REGISTER OF DEEDS

002141

Register of Deeds Stamp & File Number

For corners in  
Barry  
(County)

Located In: Corner Code ##

1. Public Land Survey

T 1N R 8W E-3

T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Daniel M. Ryan, in a field survey on September 8, 19 93,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0: 26" W. Oak, S79°E, 45 links Unknown - found twisted iron rod with  
3" Hickory, N01°W, 5 links crockery

Pratt - County Surveyor: FB#2, P6.25 30" W.Oak, N33°, 1.15 feet  
8" Apple, S56°E, 1.085 feet

Cobb-1913: Stake & 3 stones  
Found Oak stump  
Found apple still alive

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron 20704 and accepted this as a true perpetuation of the corner location.  
This corner has been used and accepted by many surveyors as the proper location of this  
corner.

SURVEY &  
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced 1/2" iron with 3/4" iron rod and aluminum remonumentation cap.  
Witness as follows:

16" Twin Hickory, S73°W, 171.65 feet, 60p nail on North side.  
36" Red Maple, S56°E, 109.0 feet, 60p nail on South side.  
Southwest corner garage found, S43°E, 174.41 feet.  
Northeast corner brick chimney @ base, S51°E, 133.41 feet.



Surveyed by [Signature] Date September 8, 1993

Surveyor's Michigan License No. 34975