

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schondelmaier
REGISTER OF DEEDS

002124

Register of Deeds Stamp & File Number

For corners in

BARRY COUNTY
(County)

Located In:

Corner Code ##

- 1. Public Land Survey
JOHNSTOWN TWP.
- 2. Property Controlling
in Section
- 3. Miscellaneous
Property in Sec.

T	<u>1N</u>	R	<u>8W</u>	<u>E-5</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR in a field survey on SEPTEMBER 1, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5 G.L.O. BLACK OAK 20" N82°W 33 LKS; WHITE OAK 10" S74°E 17 LKS.
LCRC NO. 65 JAMES L. KING RLS NO. 14766
LCRC NO. 126 JAMES L. KING RLS NO. 14766
BOTH RECORDINGS CALL FOR 5/8" SQUARE IRON, SET BY PROPORTIONAL METHODS; 28" HICKORY S55°W 51.91 FT
4" STEEL POST SOUTH 36.35 FT; 2" SOLID STEEL POST NORTH 28.96 FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 FOUND R.R. SPIKE MATCHING ABOVE WITNESSES OVER 5/8" SQUARE IRON
CORNER LOCATION FITS OCCUPATION WELL, IN CENTERLINE ± OF E/W ROAD WITH FENCES RUNNING N/S
ACCEPTED OCCUPATION AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER LOCATION AND ACCEPTED CORNER
AS PER PREVIOUS RECORDINGS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 REPLACED RR SPIKE AND 5/8" SQUARE IRON WITH STANDARD BARRY COUNTY REMONUMENT 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH 0.3 FT BELOW SURFACE
NAIL AND SPOTTER IN SE SIDE OF 30" HICKORY S66°W 51.60 FEET
NAIL AND SPOTTER IN SE SIDE OF 30" ASH S47°W 43.36 FEET
CENTER OF 2" SOLID STEEL FENCE POST N03°W 29.10 FEET
NAIL AND SPOTTER IN S SIDE OF 5" OAK N83°E 105.53 FEET
FACE OF 4" STEEL FENCE POST SOUTH 36.30 FEET

SURVEY &
REMONUMENTATION
APR 05 1994
COMMISSION



Signed by [Signature]
ROBERT R. CARR
Surveyor's Michigan License No. 20704

Date SEPTEMBER 8, 1993