

SURVEY & REMONUMENTATION

NOV 04 1996

COMMISSION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

SEP 27 10 48 AM '96

Sandy Schindelmayer
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>BARRY</u> (County) | Located In: | Corner Code # |
| JOHNSTOWN TWP. | | |
| 1. Public Land Survey | T <u>1</u> N R <u>8</u> W | E-6 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

002402

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | | | | | | | |
| 13 | | | | | | | | | | | | |

I, ROBERT R. CARR, in a field survey on DECEMBER 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. MUSGROVE EVANS, 1826.
- LCRC NO. 268, DONALD J. DAVIS, PS#17617, RECORDED MARCH 19, 1979.
- LCRC NO. 438, ROBERT R. CARR, PS#20704, RECORDED JULY 23, 1991.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 8" BY 2.5' BY 4' CONCRETE PILLAR WITH DRILL HOLE IN CENTER OF TOP AS PER LCRC NO. 268 AND LCRC NO. 438.
ACCEPTED AS BEST EVIDENCE OF ORIGINAL CORNER.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
11 March '96
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 8" X 30" X 48" CONCRETE PILLAR WITH DRILL HOLE IN CENTER OF TOP.
- FENCES RUNNING NORTH AND SOUTH.
- NAIL & SPOTTER IN NORTHERLY SIDE OF 8" BEECH S77°W 38.51 FEET.
- NAIL & SPOTTER IN NORTHEASTERLY SIDE OF 6" BEECH N61°W 41.86 FEET.
- NAIL & SPOTTER IN NORTHERLY SIDE OF 10" BEECH N83°W 10.88 FEET.
- NAIL & SPOTTER IN SOUTHERLY SIDE OF 30" BEECH N78°E 92.81 FEET.
- NAIL & SPOTTER IN SOUTHERLY SIDE OF 12" MAPLE S82°E 4.43 FEET.



Signed by Robert R. Carr Date SEPTEMBER 6, 1996
Surveyor's Michigan License No. 20704