

**SURVEY &
REMONUMENTATION**

APR 04 2000

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Barry Located In: Corner Code #
(County)

1. Public Land Survey T 1N R 8W E-10
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____



2783
Page: 1 of 1
11/15/1999 09:00A

Darla K. Burshdoff - Barry Co. LCRCR

Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL P. PRATT, in a field survey on MARCH 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GLO by Musgrove Evans, D.S. in 1826: W.O. 14 N.52 1/2 ° W, 180; Burr Oak 12 S.9°E, 250.
 - Walter Heath, C.S. in 1905: Corner Lost. Set gas pipe 40.37 chains north of restored section corner between sections 28, 29, 32, & 33. 12" Hickory N.66°E., 100 1/4; 8" Hickory S.1°E, 39 1/2.
 - Old field book of Crane Land Surveying, P.C. (probably Clyde Chambers). 107 feet East of centerline of Banfield Road. 14" Hickory, South 25.7 feet; 12" Ash, N.75°E., 45.4 feet.
 - Referenced by plat of "Country Acres" (L. 5, P. 64). No references listed.
 - Survey by Ray Moored, P.S. #26463: Found Iron 118.80 feet East of centerline of Banfield Road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find Iron referenced by Moored's Survey. Found Iron rod at intersection of North and South 1/4 line and Banfield Road. Measured east 118.80 feet and 107.0 feet and excavated to original ground and found nothing. Set 243.0 feet West of Northwest corner of "Country Acres" plat. Measures 107 feet +/- to found iron at intersection.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set standard Barry County Remonumentation Marker with Cap.
- 6.5' North of Centerline of Hickory Road.
 - 107' East of Centerline of Banfield Road
 - pk nail in S.W. side of U.P., N.62°W, 77.42'
 - Nail in S. Side of 14" Cherry, N.76°E, 97.99'
 - Nail in N. Side of 16" Cherry, S. 66°E, 101.21'
 - Nail in N.W. Side of 20" Cherry, S.20°W, 100.90'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 April '99
BRIAN REYNOLDS

MICHAEL P. PRATT
PROFESSIONAL SURVEYOR
NO. 43067

Signed by Michael P. Pratt
Michael P. Pratt, P.S.

Date 10/11/99

Surveyors Michigan License No. 43067