

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schindelmarper
REGISTER OF DEEDS

002126

Register of Deeds Stamp & File Number

For corners in

BARRY COUNTY
(County)

JOHNSTOWN TWP

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____

5. Private Claims _____

Located In:

Corner Code =#

T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____

S 9 T 1N R 8W

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

F-4

Recorded Plat _____

I, ROBERT R. CARR, in a field survey on SEPTEMBER 1, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-4 CENTER OF SECTION 9.
NO RECORD OF PREVIOUS LOCATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-4 NO EVIDENCE FOUND.
ESTABLISHED AT INTERSECTION OF 1/4 LINES.
EAST & WEST 1/4 POST ARE IN LAKES, USED MATHEMATICAL LOCATION OF MID-POINTS OF EAST & WEST SECTION LINE TO ESTABLISH EAST & WEST 1/4 LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-4 SET STANDARD BARRY COUNTY REMON. 3/4" STEEL ROD WITH ALUMINUM CAP WITH CENTER PUNCH.
NAIL & SPOTTER IN EAST SIDE OF 18" HICKORY, N15°E, 14.63 FT.
NAIL & SPOTTER IN NORTHEAST SIDE OF 20" HICKORY, N48°W, 24.13 FT.
NAIL & SPOTTER IN NORTHEAST SIDE OF 11" WALNUT, N21°W, 20.48 FT.
NAIL & SPOTTER IN NORTH SIDE OF 2" HICKORY, S65°W, 18.22 FT.
1.0'± SOUTH OF CENTERLINE OF GRAVEL DRIVEWAY.
13.5'± NORTH OF E/W FENCE LINE.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by _____

ROBERT R. CARR

20704

Date

NOV 19 1993

Surveyor's Michigan License No. _____