

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970.**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schondelmarer
REGISTER OF DEEDS

002123

Register of Deeds Stamp & File Number

For corners in

BARRY COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey
JOHNSTOWN TWP
- 2. Property Controlling
in Section
- 3. Miscellaneous
Property in Sec.

T	1N	R	8W	F-5
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, ROBERT R. CARR in a field survey on SEPTEMBER 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5 G.L.O. BLACK OAK 24" S21°E 30 LKS; BLACK OAK 18" N31°W 66 LKS.
LCRC, NO. 65 JAMES L. KING RLS NO. 14766
LCRC NO. 126 JAMES L. KING RLS NO. 14766
BOTH RECORDINGS CALL FOR 5/8" SQUARE IRON, SET BY PROPORTIONAL METHODS.
3" STEEL FENCE POST SOUTH 15.44 FT.
U-POLE N60°W 87.60 FT
14" HICKORY S05°W 12.40 FT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 FOUND 5/8 SQUARE IRON AS PER ABOVE WITNESSES.
HAVING NO OTHER RECORD OF THE PERPETUATION OF THIS CORNER AND HAVING KNOWLEDGE OF THE ABOVE LOCATION OF THIS CORNER HAVING BEEN USED EXTENSIVELY FOR SURVEYS IN SECTIONS 9 AND 16 FOR MORE THAN 20 YEARS, I ACCEPTED THE LOCATION AS A REASONABLE PERPETUATION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 REPLACED 5/8" SQUARE STEEL STAKE WITH STANDARD BARRY COUNTY REMONUMENTATION 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH.
NAIL AND SPOTTER IN SE SIDE OF 26" HICKORY S23°W 13.12 FT
NAIL AND SPOTTER IN S SIDE OF 12" ELM N74°E 119.06 FT
NAIL AND SPOTTER IN N SIDE OF U-POLE S85°W 248.44 FT
3" STEEL FENCE POST S01°W 15.44 FT TO CENTER

SURVEY &
REMONUMENTATION

APR 0 5 1994

COMMISSION



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date SEPTEMBER 8, 1993