

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schondelmarper
REGISTER OF DEEDS

002125

Register of Deeds Stamp & File Number

For corners in

BARRY COUNTY
(County)

Located In:

Corner Code =#

- 1. Public Land Survey
JOHNSTOWN TWP.
- 2. Property Controlling
in Section
- 3. Miscellaneous
Property in Sec.

T	<u>1N</u>	R	<u>8W</u>	<u>G-3</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, ROBERT R. CARR, in a field survey on SEPTEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3							⊙					
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-3 SETH PRAT, COUNTY SURVEYOR, MAY 4, 1885, SURVEY OF SECTION 4, LONG POINTED STONE.
WHITE OAK 20" S65°W 61 LINKS.
G.L.O. WHITE OAK 20" S65°W 61 LKS; BLACK OAK 10" N44°W 117 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3 FOUND 6"x9"x36" POINTED STONE IN E/W FENCE LINE.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 REPLACED STONE WITH STANDARD BARRY COUNTY REMON. 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH.
NAIL AND SPOTTER IN W SIDE OF 6" OAK S18°E 7.08 FT
NAIL AND SPOTTER IN W SIDE OF 8" OAK S19°W 6.84 FT
NAIL AND SPOTTER IN E SIDE OF 38" OAK N30°E 50.25 FT
NAIL AND SPOTTER IN N SIDE OF 24" CHERRY N80°W 94.5 FT



Signed by [Signature]
ROBERT R. CARR
Surveyor's Michigan License No. 20704

Date SEPTEMBER 8, 1993