

STATE OF MICHIGAN
 COUNTY OF BARRY
 BARRY COUNTY REMONUMENTATION RECEIVED FOR RECORD
 LAND CORNER RECORDATION CERTIFICATE DEC 7 3 41 PM '93
 Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmaier
 REGISTER OF DEEDS

002122

Register of Deeds Stamp & File Number

For corners in:

BARRY COUNTY
 (County)
 JOHNSTOWN TWP

Located In:	Corner Code #
T 1N R 8W	G-5
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling In Section
- Miscellaneous Property in Sec.
- Lot No. , Recorded Plat
- Private Claims

I, ROBERT R. CARR in a field survey on SEPTEMBER 1, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-5 C.L.C.
 PLAT OF "LONGVIEW".
 PLAT OF "SHADY SHORES".
 PLAT OF "VAL-PINE".
 CLO ELM 6" S54°W 32 LKS.
 TAMERACK 10" N63°W 72 LKS.
 DONALD J. DAVIS, SEPT. 20, 1978, SURVEY RECORDED LIBER 1, PAGE 498.
 5/8" IRON: U-POLE S35°E 39.8'.
 U-POLE N20°E, 38.61'.
 U-POLE N40°W, 62.83'.
 SURVEY BY DONALD J. DAVIS, JAN 22, 1993, JOB NO. 9583 SHOWING REFERENCE TO PLAT OF "LONGVIEW".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 FOUND 1" X 3/8" PIPE 1.7' BELOW SURFACE WITH STONES AROUND AND REMAINS OF FENCE RUNNING EAST & WEST THROUGH DIG.
 FOUND U-POLE S35°E, 39.8' (DAVIS, 1978).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 REPLACED PIPE WITH STANDARD BARRY COUNTY REMON. 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH.
 NAIL & SPOTTER IN SW SIDE OF U-POLE S35°E, 39.8 FT.
 NAIL & SPOTTER IN SE SIDE OF U-POLE N75°E, 22.95 FT.
 FACE OF TELEPHONE RIZER N25°E, 38.95 FT.
 13'± SOUTH OF CENTERLINE OF E/W ROAD.

SURVEY &
 REMONUMENTATION

APR 05 1994

COMMISSION



Signed by Robert R. Carr
 ROBERT R. CARR
 Surveyor's Michigan License No. 20704

Date Nov 10, 1993