

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Survey &
REMONUMENTATION

APR 04 2000

SECTION

For Corners in BARRY (county)

Located In: _____ Corner Code # _____

1. Public Land Survey T 1N R 8W I-1
 CORNER COMMON TO _____
 SECTIONS 2 & 3 _____
 JOHNSTOWN TOWNSHIP _____
 ON TOWNSHIP LINE _____

2. Property Controlling _____
 in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____ Recorded Plat _____

5. Private Claims _____



2811
Page: 1 of 1
12/07/1999 08:36

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 8 NOVEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE DEPUTY SURVEYOR MUSGROVE EVANS, 1826, "...NORTH BOUNDARY 37 LKS EAST OF POST" "A. W. ASH 8 S46W 30 ELM 10 S46 1/2E 40 LKS"
 - NO RECORD OF THIS CORNER APPEARS IN THE COUNTY SURVEYOR RECORDS.
 - LAND CORNER RECORDATION CERTIFICATE #123 BY JAMES L. KING, P.S. #14766, 1974, "SET BY PROPORTIONAL METHODS. W END OF BRIDGE EAST 21.5' 10" WALNUT N88°E 55.64 FEET 6" WALNUT N20°E 48.02' 3' N OF C/L EAST & WEST ROAD 24' EAST OF CENTERLINE OF ROAD TO NORTH 24.43' E OF SE COR. SEC. 34 BALTIMORE
 - PRIVATE NOTES FROM DeKEYSER FILES. C.D. PIKE, MAY 1973, RECITE SAME WITNESSES AS ITEM #3 ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRONS REPRESENTING I-13 AND I-1 T1N R8W AS RECITED BY KING (ITEM #3 & #4 ABOVE). ALSO FOUND WELL POINT FOR THE STANDARD CORNER AT G-13, T2N, R8W, BALTIMORE TOWNSHIP. TRAVERSED THE NORTH LINE OF SECTION 3 AND FOUND NO MONUMENTATION AT H-13 OR H-1 (T1N, R8W). TRAVERSED THE TOWN LINE FURTHER EAST TO I-13, FOUND AN IRON SET BY KING IN REFERENCE TO AN ORIGINAL GLO WITNESS. BASED ON REVIEW OF MEASUREMENTS AND OCCUPATION LINES, DISREGARDED FOUND MONUMENTS AT I-13 & I-1 BY KING. RESTORED I-13 AT LOCATION THAT BEST FIT ALL MEASUREMENTS AND OCCUPATION. RESTORED I-1 AT GOVERNMENT JOG ON TOWN LINE. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A 10" LOCUST N42°E 37.17' FOUND NAIL W/METAL TAG IN THE NORTHWEST SIDE OF A 32" WALNUT S01°W 18.09' SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A 32" WALNUT S01°W 18.58' SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A 12" WALNUT S65°W 31.23' EAST SIDE OF A STOP SIGN POST (BASE) N23°W 55.40' CENTERLINE OF WESTERNMOST OF 2 48" CMP CULVERTS EAST 50'± 1/2" IRON AS RECORDED BY JAMES KING IN L.C.R.C. #123 LIES EAST 17.57' I-13, T2N, R8W, LIES WEST 24.42' CORNER LIES 9'± EAST OF CENTERLINE TO THE NORTH CORNER LIES 2'± SOUTH OF EAST-WEST CENTERLINE



ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
8 Nov. '99
BRIAN REYNOLDS COUNTY SURVEYOR

Signed by [Signature]
Surveyor's Michigan License No 31602

Date DEC 3, 1999
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 197