

SURVEY & REMONUMENTATION

FEB 17 1998

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BARRY

(County)

Located in:



Sandy Schondelmayer - Barry Co. LCRCR

2652

Page: 1 of 1
12/16/1997 12:20P

JOHNSTOWN TOWNSHIP, SECTION 23

- 1. Public Land Survey T 1N R 8W 1 - 7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert R. Carr, in a field survey on May 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.L.O., Musgrove Evans D.S., 1826
- 2. Cobb, 1893, Found stake and brick, set stone, brick and iron, Sugar 3 N82-1/2E 36-1/2, Hick 8 S80-1/4W 41.
- 3. L.C.R.C. File no. 237 by Robert R. Carr, June 12, 1976.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1. No evidence of G.L.O. bearings.
- 2. Both bearings from Cobb 1893 still standing
Now 36" +/- Maple and 36" +/- Hickory
- 3. Found 5/8" Iron per L.C.R.C. File no. 237 by Carr
With bearings remaining and matching bearings
By Cobb 1893, dug below iron to 3' +/- deep,
No evidence of stone or brick, road excavation evident.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 July, '96
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 5/8 iron as true perpetuation of corner and place Barry County Remonumentation stake and cap in monument box, from which bears;
18" Shag bark Hickory, S42degW 43.51' set spotter
30" Maple, S87degW 26.51' set spotter
30" Maple, N37degE 45.35' set spotter
20" Walnut, S64degE 27.07' set spotter
0.80' +/- West of centerline of Road.



Signed by [Signature]
Surveyor's Michigan License No. 20704

Date NOV 10, 1997