

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

SECTION

For Corners in
BARRY
(county)

1. Public Land Survey
1/4 CORNER COMMON TO
SECTIONS 26 & 27
JOHNSTOWN TOWNSHIP

2. Property Controlling
in Section

3. Miscellaneous

4. Lot No _____ Recorded Plat _____

5. Private Claims _____

Located In: Corner Code #

T 1N R 8W I-10

T _____ R _____

T _____ R _____

T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

2848
Page: 1 of 1
12/27/1999 01:44P

Daria K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Brian Reynolds, in a field survey on 25 MARCH, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S. 1826 (R8W, P. 17) B. OAK 14 N44 1/2E 24 W. O. S65W 26
 - COUNTY SURVEYOR RECORDS: FRANK BOWEN, 1876 (L,1, P.134) "STONE FOR CORNER" B. OAK 10 N76W 39 W. OAK 30 N71E 62
 - COUNTY SURVEYOR RECORDS: A. C. WILLSON, JANUARY 1868 (L.2, P.203) "FOUND ORIGINAL BEARINGS"

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND "PK" NAIL NEAR CENTERLINE OF NORTH-SOUTH BITUMINOUS ROAD AT APPARENT CORNER LOCATION. TRAVERSED ENTIRE LINE BETWEEN I-9 AND I-11 (AS WELL AS ALL OF SECTION 26), TYING IN OCCUPATION. IT APPEARS THAT THE "PK" NAIL WAS PLACED AT THE MID-POINT OF THE LINE I-9 TO I-11 PRIOR TO THE REMONUMENTATION OF I-9 (WHICH WAS RESTORED AT A LOCATION 2.2 FEET SOUTHWEST OF A PREVIOUSLY RECORDED 1/2" IRON AT THE SURFACE). EXCAVATED BELOW BITUMINOUS ROADWAY AT MID-POINT OF TRUE LINE, TO A DEPTH OF ABOUT 2.5', THE EXCAVATION INCLUDING THE POSITION OF THE FOUND "PK", FOUND NO EVIDENCE OF PRIOR MONUMENTATION. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP AT MID-POINT ON LINE BETWEEN RESTORED I-9 AND RESTORED I-11, AND INSTALLED MONUMENT BOX.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
 - SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A UTILITY POLE N69°E 37.61'
 - SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 24" OAK N24°W 43.96'
 - SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OA A 16" OAK N66°W 22.28'
 - SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 30" OAK S49°W 29.52'
 - TOP CENTER OF A CONCRETE FILLED CORNER POST S88°E 35'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12/14/99 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date DEC 27, 1999