

SURVEY & REMONUMENTATION

FEB 17 1998

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY (County) JOHNSTOWN TWP.

Located In:



C

Sandy Schondeimayer - Barry Co. LCRCR

2655

Page: 1 of 1 12/16/1997 12:20P

- 1. Public Land Survey T 1N R 8W J-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on APRIL 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 MUSGROVE EVANS D.S. TAM 9" N58°E 5 LKS; TAM 12" S30°W 11LKS
1893 COBB, FOUND OLD STAKE FROM U.S. BEARING, SET STONE ELM, 6" N11-1/4°W 15-1/2 LKS; B. ASH 6" N66°E 27 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" PIPE 1.5 FEET DEEP WITH 1/2" IRON IN CENTER IN LOW WET AREA, PROBED EXTENSIVELY FOR STONE, BUT DID NOT FIND. FOUND PIECES OF OLD FENCE WIRE IN EAST AND WEST DIRECTIONS FROM 2" PIPE ACCEPTED 2" PIPE AS BEST EVIDENCE OF CORNER AND REPLACED 1/2" IRON WITH BARRY COUNTY REMONUMENTATION STAKE AND CAP WITH RING OF STONES.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 8 July '96 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP IN 2" PIPE WITH RING OF STONES AROUND SET SPOTTER IN 16" OAK, S19°E 62.10 FEET; SET SPOTTER IN 30" OAK, S34°E 88.42 FEET; SET SPOTTER IN 24" OAK, N52°W 129.87 FEET; SET SPOTTER IN 10" OAK, N49°E 13.53 FEET; SET SPOTTER IN 30" OAK, N18°E 39.93 FEET; CENTERLINE OF GRAVEL ROAD WEST 55 FEET MORE OR LESS.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and a black dot at row 7, column I.

Signed by [Signature]

Date NOV 10 1997

