

SURVEY & REMONUMENTATION

FEB 17 1998

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

SECTION

BARRY

(County)

JOHNSTOWN TOWNSHIP

Located In:



Sandy Schondelmayer - Barry Co. LCRCR

2656

Page: 1 of 1
12/16/1997, 12:20P

1. Public Land Survey

T 1N R 8W J-8

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, ROBERT R. CARR, in a field survey on APRIL 24, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CENTER OF SECTION NOT SET WITH ORIGINAL GOVERNMENT SURVEY
NO PREVIOUS RECORD OF AN ESTABLISHED LOCATION.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

INTERSECTED 1/4 LINE AND PLACED BARRY COUNTY REMONUMENTATION STAKE AND CAP AT INTERSECTION POINT.
LOCATION IS 30' M/L SOUTH OF EAST-WEST FENCE AND 30' M/L WEST OF REMAINS OF NORTH-SOUTH RENCE.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 July '96
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP
SET SPOTTER IN 30" OAK, N28°W 35.26 FEET;
SET SPOTTER IN 8" OAK, N88°W 18.27 FEET
SET SPOTTER IN 8" OAK, S05°W 16.04 FEET;
FEET M/L SOUTH OF EAST-WEST FENCE
30 FEET ML WEST OF FALLEN NORTH-SOUTH FENCE.



Signed by [Signature]
Surveyor's Michigan License No. 20704

Date NOV 10, 1997