

SURVEY & REMONUMENTATION

FEB 17 1998

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

BARRY
(County)

Located In:

Cc



Sandy Schonheimayer - Barry Co. LCRCR

2650
Page: 1 of 1
12/16/1997 12:20P

JOHNSTOWN TOWNSHIP

1. Public Land Survey

T 1N R 8W K-8

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, ROBERT R. CARR, in a field survey on APRIL 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826 MUSGROVE EVANS D.S.
TAM 6" N70°W 16 LKS; TAM 8" N35°E 12 LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

BISECTED EAST LINE OF SECTION 23 TO LOOK FOR CORNER. LOCATION FALLS IN TAMARAC SWAMP, WATER 2 FEET M/L DEEP. FOUND BARB WIRE FENCES RUNNING NORTH AND EAST FROM TREE STUMP USED AS FENCE CORNER. MIDPOINT OF EAST SECTION LINE IS 13 FEET SOUTH AND 13 FEET EAST OF TREE STUMP FENCE CORNER.

CONSIDERED CORNER LOST AND SET BARRY COUNTY REMONUMENTATION STAKE AND CAP AT MIDPOINT BETWEEN NORTHEAST AND SOUTHEAST CORNERS OF SECTION 23.


ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 July, '96
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP
NORTHEAST CORNER OF SECTION 23, NORTHERLY 2626.39 FEET;
SOUTHEAST CORNER OF SECTION 23, SOUTHERLY 2626.39 FEET
SET SPOTTER IN 16" MAPLE, N35°W 151.08 FEET;
SET SPOTTER IN TRIPLE 28", 24" & 16" MAPLE, N25°E 270.59 FEET;
SET SPOTTER IN 24" MAPLE, S05°E 370.45 FEET;
13 FEET M/L SOUTH OF BARBWIRE FENCE TO EAST;
13 FEET M/L EAST OF BARBWIRE FENCE TO NORTH; IN SWAMP.



Signed by [Signature]
Surveyor's Michigan License No. 20704

Date NOV. 10, 1997