

**SURVEY & REMONUMENTATION**

FEB 17 1998

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

BARRY  
(County)

Located In:



**2651**

Page: 1 of 1  
12/16/1997 12:20P

Sandy Schondelmayer - Barry Co. LCROR

JOHNSTOWN TOWNSHIP

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>1N</u> R <u>8W</u> | <u>K-9</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on APRIL 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1826 MUSGROVE EVANS, D.S. W.O. 12 S9°W LKS, DO S79°W 50 LKS.  
1868 A.C. WILLSON, FOUND CORNER BY BEARINGS, SET STAKE, STONE AND BRICK  
BARRY COUNTY ROAD COMMISSION, NO DATE  
18" WALNUT N30°W 32.7'; 18" LOCUST N5°E 42.0'; T. POLE N30°E 51.0'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND RAIL ROAD SPIKE AT SURFACE OF BITUMINOUS ROAD  
FOUND HUMP IN GROUND WHICH APPEARS TO BE ROTTED STUMP OF 18" WALNUT  
FOUND STUMP OF 18" LOCUST  
BEARINGS AND DISTANCES CHECK TO RAILROAD SPIKE  
T. POLE GONE  
DUG BUT COULD NOT FIND STONE  
ACCEPTED RAILROAD SPIKE AS FAITHFUL PERPETUATION OF CORNER AND SET BARRY COUNTY REMONUMENTATION STAKE AND CAP.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
8 July '96 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

BARRY COUNTY REMONUMENTATION STAKE AND CAP IN MONUMENT BOX  
20" WALNUT, S34°W 59.60 FEET  
TWIN 8" & 10" WALNUT, N70°E 70.48 FEET  
14" WALNUT, N36°E 37.30 FEET  
24" WALNUT, N61°W 61.40 FEET  
NORTHEAST CORNER OF HOUSE FOUNDATION, S50°W 126.83'



Signed by [Signature]  
Surveyor's Michigan License No. 20704

Date NOV 10, 1997