

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 4 26 PM '93

Sandy Schendelmarer

REGISTER OF DEEDS

002142

Register of Deeds Stamp & File Number

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
(County)

Located In:

Corner Code #

1. Public Land Survey

T	2N	R	7W	A-13
T	2N	R	8W	M-13
T	1N	R	7W	A-1
T	1N	R	8W	M-1
S		T		
S		T		
S		T		
S		T		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Daniel M. Ryan, in a field survey on September 8, 19 93,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 8" Beech, N48°E, 62 links
15" B. Ash, N46°W, 45 links
County Surveyor: Set stone, iron & glass
no name, date or witnesses
Robert R. Carr: Set 1/2" Rebar
14" Maple, S45°W, 40.80 feet
16" Maple, N75°W, 82.80 feet
Corner cem. fence, N45°E, 37.50 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar in Monument box.
20" Maple (formerly 16"), N52°W, 82.80 feet
1/2" rebar set in 1985 survey by RELS# 14766-James L. King

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" rebar with 3/4" pin and aluminum remonumentation cap.
Nail and Barry County Shiners set as follows:

South side of 30" Maple, S75°E, 71.00 feet.
West side of 16" Elm, N15°E, 107.11 feet.
South side of 20" Maple, N52°W, 82.81 feet.
West side of P-pole, S70°W, 161.24 feet.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by [Signature] Date September 8, 1993

Surveyor's Michigan License No. 34975