

REMONUMENTATION

MAY 20 1997

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECORDS DEPARTMENT

DEC 9 2 09 PM '96

Sandy Schonfeldmayer
REGISTER OF DEEDS

002417

Register of Deeds Stamp & File Number

- For Corners in BARRY Located In: Corner Code #
- Public Land Survey
1/4. COR. COMMON TO
SEC'S. 5 & 6
BARRY TWP. T..1N R..9WC-2.....
T..... R.....
T..... R.....
T..... R.....
 - Property Controlling
in Section S.....T..... R.....
S.....T..... R.....
 - Miscellaneous
Property in Sec. S..... T..... R.....
S..... T..... R.....
 - Lot No....., Recorded Plat.....
 - Private Claims.....

I, RAYMOND MOORED, in a field survey on MARCH, 1994 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
SEE BACK OF THIS FORM FOR PART A

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
CORNER GONE DUE TO SEWER CONSTRUCTION. RESET CORNER FROM EXISTING OLD WITNESSES AND AN ADJACENT BOUNDARY SURVEY BY BRIAN REYNOLDS, P.S. ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

- NAIL IN SW SIDE POWER POLE N20°W 22.98'
- SE COR BRICK BLDG (FIRE BRN) N10°W 75.33'
- WEST EDGE MANHOLE RIM N85°E 23.65'
- EAST EDGE STOP/STREET SIGN POST S50°E 60.50'
- NAIL IN SW SIDE 28" MAPLE S60°E 66.35'



Signed by *Raymond Moored*

Date.....12/2/96.....

Surveyor's Michigan License No.....26463.....

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

9 OCT. 95

BRIAN REYNOLDS

COUNTY SURVEYOR

2417-A

PLAT 14 POST, SECTION 5, T1N, R9W (C-2)

PLAT 14 CONTINUED:

JO SYLVESTER SIBLEY D.S. 1826 (R9W, P.39) A YELLOW OAK 26 S1W 42 A W OAK 12 S85W 32.
COUNTY SURV. REC. (BROWN BARRY TWP FIELD BOOK, P86) PRATT SEPT. 1888 (L.1, P.333) SERIES #7 LIME STONE
W/BROKEN CROCKERY AROUND IT "COBB 1887". LIME STONE 8'X5'X3' OAK STAKE & BROKEN CROCKERY. (F.S. BOWEN
COPYIST) (L2, P.36) BEARINGS FOUND-NO NAME OR DATE.
LEE S. COBB 1887 (L2, P.262) LIME STONE WITH BROKEN CROCKERY & STONE AROUND IT. OAK STAKE ON S. SIDE.
BATEMAN JULY 31, 1900 (L.2, P.309) FOUND POST & DROVE AN IRON.
COUNTY ROAD COMM. (1927 ORCHARD & PIFER RD. #412 P.3) P.I. STA. 6&85.0 15" MAPLE - S 53 DEG W - 41.6 IRON:
16" MAPLE - N16 DEG - 28.0. 8" HICKORY - N26 - 30W - 29.6. 16" MAPLE - N55.4 16" HICKORY - N20 DEG W - 29.3. 36"
MAPLE - S30 DEG W - 40.35 (NAIL IN TREES 2-8-73)

ACT 132 SURVEY L.1, P.164-165) 2-19-1974 ALLEN H. MC MACHEN RLS # 16935
DELTON LEE COBB 20 OCT 1887 LIME STONE 8X3X5 INCHES WITH BROKEN CROCKERY & STONE AROUND IT. AND OAK
STAKE ON SOUTH SIDE (LIBER 1 OF PLATS, PAGE 29)
BLACKMAN & BUSHES FIRST ADDITION TO THE VILLAGE OF DELTON REFERENCED - NO WITNESSES LEE COBB 16 AUGUST 1888
(LIBER 1 OF PLATS, PAGE 33)
BLACKMAN & BUSHES ADDITION TO THE VILLAGE OF DELTON REFERENCED-NO WITNESSES. LEE COBB 28 JAN 1892
(LIBER 1 OF PLATS, PAGE 39)
BILL SMITH PLAT WILLIAM ROGERS RLS # 6197 3 SEPT 1957-REFERENCED-NO WITNESSES (LIBER 4 OF PLATS, PAGE
28)
BARRETT ACRES JOHN H. ALDEN RLS # 8885 24 MARCH 1958-REFERENCED-NO WITNESSES (LIBER 4 OF PLATS, PAGE
30)

SURVEY &
RECORDS DIVISION

MAY 20 1997

COMMISSION