

SURVEY & REMONUMENTATION

MAY 20 1997

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED

Dec 9 2 09 PM '96

For corners in **COMMISSION**

Sandy Schindelmarjer
REGISTER OF DEEDS

<u>BARRY</u> (County)	Located In:	Corner Code #
1. Public Land Survey SEC COR. COMMON TO SEC'S 5&8 BARRY TWP.	T <u>1</u> N <u>R</u> 9 W	<u>D-3</u>
2. Property Controlling in Section	T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

002419

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RAYMOND MOORED, in a field survey on MAY, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3			●									
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO SYLVESTER SIBLEY D.S. 1826(R9W,P.38)A W. OAK 30 S26W 6 A Y OAK 26 N15E 67. COUNTY SURVEYOR REC. WILLSON (BROWN BARRY TWP. F.B,P.84) P. 37-38. FOUND BY OLD BEARINGS TOOK NEW: W OAK 6 N23W 61 Y OAK 24 S85W 46. COUNTY ROAD COMM. (PLEASANT LAKE ROAD F.B, PAGE 1 NO DATE) FOUND IRON. FNC POST W 30.0' 20" HICKORY S30E 71.7' 18 HICKORY S30W 57.2'. (ACT 132 SURVEY L.1,P.158) 1-2-74 JOHN M. BUDZIK RLS.#18982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" IRON IN ROAD ON OCCUPATION LINES E & W. FENCE POST WITNES FROM ROAD COMMISSION NOTES ABOVE CHECKED. ACCEPTED FOUND POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.


ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

9 OCT. '95
BRIAN REYNOLDS

ISR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
- NAIL & TAG N SIDE 26" HICKORY WEST 39.93'
- NAIL & TAG N SIDE 30" HICKORY S45DEG. W 28.04'
- NAIL & TAG N SIDE E SIDE 30" OAK N30 DEG W 82.83'
- NAIL & TAG S SIDE 8" ELM S85DEG E. 35.36'
- FACE OF OLD WOOD POST WEST 30.0'



Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 11/4/96