

**SURVEY & REMONUMENTATION**

SEP 13 1994

COMMISSION

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAR 16 4 24 PM '94

Sandy Schindelmarer  
REGISTER OF DEEDS

002186

Register of Deeds Stamp & File Number

For corners in BARRY  
(County)

Located In: Corner Code #

1. Public Land Survey
  - T IN R 9W E-4
  - T BARRY TWNSP.
  - T 1/4 COR. SEC. 8 & 9
  - T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous Property in Sec.
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BRIAN REYNOLDS, in a field survey on 8 FEB, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: SYLVESTER SIBLEY D.S., 1826 (R9W, Pg. 30-31)
- A B. OAK - 10 - S1E - 9.00ch.
- A TAMERACK - 10 - N53E - 1.24ch.
- NO OTHER RECORD FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**-FOUND OLD WOODEN FENCE CORNER IN MARSH; TRACES OF WOVEN WIRE FENCE RUNNING EAST & SOUTH; FENCE CORNER FITS EAST - WEST 1/4 LINE OCCUPATION AND ALSO FITS DOUBLED 1/8 LINE DISTANCE. ACCEPTED OLD WOODEN FENCE CORNER AS BEST EVIDENCE OF PERPETUATION OF 1/4 CORNER.**

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

MARCH 1, 1994 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET BARRY Co. REMONUMENTATION MONUMENT:
- MONUMENT SET AT BASE OF WOODEN FENCE CORNER:
- WITNESS TREES NOT READILY AVAILABLE.
- 1/2" IRON ON EAST - WEST 1/4 LINE AT MARGIN OF MARSH - S88-33-01E - 432.42'
- 1/2" IRON ON SECTION LINE AT MARGIN OF MARSH - S1-07-51E - 526.28



Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date MARCH 8, 1994