

SURVEY & REMONUMENTATION

SEP 13 1994

COMMISSION

For corners in BARRY
(County)

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

MAR 16 4 24 PM '94

Sandra Schindelmar
REGISTER OF DEEDS

002188

Register of Deeds Stamp & File Number

- Located In: _____ Corner Code # _____
- T IN R 9W E-5
T BARRY TWP. N. S. P.
T COR. SEC. 8 - 9 - 16 - 17
1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, BRIAN REYNOLDS, in a field survey on 21 FEB, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: SYLVESTER SIBLEY D.S., 1826 (R9W, Pg. 30)
A W. OAK - 18 - S50E - 10ch.
A B. OAK - 9 - N46W - 31ch.

-NO RECORD IN COUNTY SURVEYOR'S NOTES

-NO OTHER RECORD FOUND

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

MARCH 1, 1994 BSR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-NO RECORD OF CORNER SINCE G.L.O.. COMPUTED POINT BY DOUBLING DISTANCE BETWEEN S1/4 CORNER AND OCCUPATION AT S1/8 CORNER OF SOUTHWEST 1/4 AND HOLDING LINE BETWEEN THEM. FOUND INTERSECTING FENCE EAST - WEST AND SOUTH FITTING COMPUTED POINT WELL EAST AND WEST, BUT 10' SOUTH. LATER CHECK WITH S1/8 LINE OCCUPATION SHOWED FENCE INTERSECTION AS BEST FIT FOR DOUBLED DISTANCE FROM WEST 1/4 CORNER. TOOK INTERSECTION OF FENCES E. - W. - S. AS BEST EVIDENCE OF SECTION CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET BARRY Co. REMONUMENTATION MONUMENT:
MONUMENT SET AT INTERSECTION OF FENCES E. - W. - S.:
N&T - SW. FACE - 20" OAK - N30W - 17.92'
N&T - NW. FACE - 10" OAK - S45W - 14.60'
N&T - E. FACE - 30" TRIPLE OAK - S15E - 20.46'
N&T - NE. FACE - 8" TWIN HICKORY - S45E - 31.31'
N&T - N. FACE - 12" OAK EAST - 15.26'



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date MARCH 8, 1994